


AD-A101 252

GANNETT FLEMING CORDRAY AND CARPENTER INC. HARRISBURG PA F/G 13/13  
NATIONAL DAM INSPECTION PROGRAM. DUCK HARBOR POND DAM (NDI ID N--ETC(U)  
MAY 81 F FUTCHKO DACW31-81-C-0018

NL

UNCLASSIFIED

for  
AD-A101 252



END  
DATE  
FILED  
8-81  
DTIC

FLYING KITE

National Dam Inspection Program.  
Duck Harbor Pond Dam (NDI ID Number  
PA-00144, DER ID Number 64-54), Dela-  
ware River Basin, Little Equinunk Creek,  
Wayne County, Pennsylvania. Phase I  
Inspection Report.

DELAWARE RIVER BASIN

LITTLE EQUINUNK CREEK, WAYNE COUNTY

PENNSYLVANIA

DUCK HARBOR POND DAM

NDI ID No. PA-00144

DER ID No. 64-54

DUCK HARBOR LUMBER AND CHEMICAL CO., INC.

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

Accession For	
NTIS	CR&I
DTIC TAB	<input checked="" type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
<i>[Handwritten signature]</i>	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

Prepared by

GANNETT FLEMING CORDDRY AND CARPENTER, INC.  
Consulting Engineers  
P.O. Box 1963  
Harrisburg, Pennsylvania 17105

For

DEPARTMENT OF THE ARMY  
Baltimore District, Corps of Engineers  
Baltimore, Maryland 21203

MAY 1981

## PREFACE

This report is prepared under guidance contained in Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

DUCK HARBOR POND DAM  
NDI ID No. PA-00144; DER ID No. 64-54  
PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

CONTENTS

	<u>Description</u>	<u>Page</u>
	Brief Assessment of General Condition and Recommended Action . . . . .	111
SECTION 1	- Project Information. . . . .	1
SECTION 2	- Engineering Data . . . . .	6
SECTION 3	- Visual Inspection. . . . .	7
SECTION 4	- Operational Procedures . . . . .	9
SECTION 5	- Hydrology and Hydraulics . . . . .	10
SECTION 6	- Structural Stability . . . . .	12
SECTION 7	- Assessment, Recommendations, and Proposed Remedial Measures . . . . .	14

APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Checklist - Engineering Data.
B	Checklist - Visual Inspection.
C	Photographs.
D	Hydrology and Hydraulics.
E	Plates.
F	Geology.

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

BRIEF ASSESSMENT OF GENERAL CONDITION

AND

RECOMMENDED ACTION

Name of Dam: Duck Harbor Pond Dam  
NDI ID No. PA-00144  
DER ID No. 54-54

Size: Intermediate (12.5 feet high;  
1,103 acre-feet)

Hazard Classification: Significant

Owner: Duck Harbor Lumber and Chemical Co., Inc.  
Mr. Melvin Hill, President  
RD 1  
Equinunk, PA 18417  
Attention: Mr. Joel Hill, Secretary

State Located: Pennsylvania

County Located: Wayne

Stream: Little Equinunk Creek

Date of Inspection: 14 April 1981

Based on the criteria established for these studies, Duck Harbor Pond Dam is judged to be in good condition. The recommended Spillway Design Flood (SDF) for the size and hazard classification of the dam varies between 1/2 of the Probable Maximum Flood (PMF) and the PMF. The selected SDF is the 1/2 PMF. The existing spillway will pass only about 13 percent of the PMF before overtopping of the dam occurs. The spillway capacity is rated as inadequate.

A few deficiencies were observed, all of which are considered to be minor. Maintenance of the dam is good.

The following remedial measures, listed in approximate order of priority, are recommended to be undertaken by the Owner without delay:

(1) As part of the regular maintenance program, remove trees growing along the toe of the dam and replace the missing stones at the top of the dam.

(2) Expand the regular inspection program to include monitoring of seepage and concrete spalling. Take appropriate action if conditions worsen.

In addition, the Owner should institute the following operational and maintenance procedures:

(1) Develop a detailed emergency operation and warning system for Duck Harbor Pond Dam. When warnings of a major storm are given by the National Weather Service, the Owner should activate the emergency operation and warning system.


(2) During periods of unusually heavy rains, provide round-the-clock surveillance of the dam.

(3) As presently required by the Commonwealth, initiate a program of formal annual inspections by a professional engineer experienced in the design and construction of dams. Utilize the inspection results to determine if remedial measures are necessary.

DUCK HARBOR POND DAM

Submitted by:

GANNETT FLEMING CORDDRY  
AND CARPENTER, INC.



*Frederick Futchko*  
FREDERICK FUTCHKO  
Project Manager, Dam Section

Date: 18 June 1981

Approved by:

DEPARTMENT OF THE ARMY  
BALTIMORE DISTRICT, CORPS OF  
ENGINEERS

*James W. Peck*  
JAMES W. PECK  
Colonel, Corps of Engineers  
Commander and District Engineer

Date: 24 JUNE 1981

DUCK HARBOR POND DAM



Overview

DUCK HARBOR POND DAM

NDI ID No. PA-00144; DER ID No. 64-54

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

SECTION 1

PROJECT INFORMATION

1.1 General.

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Duck Harbor Pond Dam is a dry masonry dam with a concrete cutoff wall along the upstream face. The dam is 155 feet long and 12.5 feet high.

The main spillway is a concrete paved section located near the center of the dam. The weir crest is 11.4 feet long and 1.8 feet below the top of the dam. A dry masonry ramp that is paved with concrete extends downstream from the dam at the main spillway. This structure acts as a spillway chute. The remainder of the top of the dam is dry stone masonry about 15 feet wide and acts as an auxiliary spillway. The elevation along the auxiliary spillway is variable. The outlet works consists of a 4-foot wide by 6.2-foot high rectangular opening just to the right of the main spillway. At the upstream end of the opening, concrete anchors two vertical timber posts to the upstream concrete facing. The posts are set with a 2.0-foot clear opening. Stoplogs are placed across this opening. The top elevation of the stoplogs, which can be varied, controls pool elevation.

The various features of the dam are shown on the photographs in Appendix C and on the plates in Appendix E. A description of the geology is included in Appendix F.

b. Location. Duck Harbor Pond Dam is located on Little Equinunk Creek in Damascus Township, Wayne County, Pennsylvania. The dam is shown on USGS Quadrangle, Long Eddy, Pennsylvania-New York, at latitude N 41° 45.2' and longitude W 75° 12.0'. The upstream end of the reservoir is shown on USGS Quadrangle, Galilee, Pennsylvania. The dam is 2.0 miles southwest of Lookout, Pennsylvania. A location map is shown on Plate E-1.

c. Size Classification. Intermediate (12.5 feet high, 1,103 acre-feet).

d. Hazard Classification. Downstream conditions indicate that a significant hazard classification is warranted for Duck Harbor Pond Dam (Paragraphs 3.1e and 5.1c(5)).

e. Ownership. Duck Harbor Lumber and Chemical Co., Inc., Mr. Melvin Hill, President, RD 1, Equinunk, PA 18417, Attention: Mr. Joel Hill, Secretary.

f. Purpose of Dam. Recreation and water supply for sawmill.

g. Design and Construction History. Duck Harbor Pond Dam was originally constructed circa 1905 to 1907 to replace a dam that had been breached. The remains of the breached dam are about 200 feet downstream from the existing structure. The Owner, whose family has always owned the dam, recounted stories of the dam being built by hand-labor, using oxen to move the massive dry stone masonry. The Commonwealth first made note of the dam in 1917, when they prepared a brief report on it. No recommendations were forthcoming from that report. Subsequently, the dam was inspected periodically by the Commonwealth. The structure had deteriorated quite severely by 1948, when the Commonwealth ordered repairs to be made. The Owner complied. Another inspection by the Commonwealth in 1965 indicated that further maintenance was required. The Owner again complied with the orders of the Commonwealth.

The Owner stated that, within the last 5 years, the upstream concrete face had been replaced. He described the face as having been placed in a trench that was at least 5 feet deep. He also stated that the outlet works was completely rebuilt in October 1979. Judging by the photographs in the PennDER files, the ramp downstream from the main spillway was built sometime between 1965 and the present.

h. Normal Operational Procedure. The reservoir pool is maintained at the main spillway crest level with excess inflows discharging over the spillway. Although the downstream mill has not been used for a number of years, the outlet works is capable of being operated to supply water to the downstream mill dam. During the fall and winter months, the pool is maintained about 3 feet below main spillway crest.

1.3 Pertinent Data.

a. <u>Drainage Area.</u> (square miles)	3.5
b. <u>Discharge at Damsite.</u> (cfs)	
Maximum known flood	Unknown
Outlet works at maximum pool elevation	160
Spillway capacity at maximum pool elevation	
Main	85
Auxiliary	102
Total	187
c. <u>Elevation.</u> (feet above msl.)	
Top of dam	1393.8
Maximum pool	1393.8
Normal pool (main spillway crest)	1392.0
Auxiliary spillway crest	Varies
Upstream invert outlet works	Unknown
Downstream invert outlet works	1381.3
Streambed at toe of dam	1381.3
d. <u>Reservoir Length.</u> (miles)	
Normal pool	1.21
Maximum pool	1.22
e. <u>Storage.</u> (acre-feet)	
Normal pool	728
Maximum pool	1,103
f. <u>Reservoir Surface.</u>	
Normal pool	204
Maximum pool	214

g. Dam.

<u>Type</u>	Dry stone masonry.
<u>Length (feet)</u>	155, including spillways.
<u>Height (feet)</u>	12.5
<u>Top Width (feet)</u>	Approx. 15
<u>Side Slopes</u>	
Upstream	3V on 1H
Downstream	Vertical
<u>Zoning</u>	None
<u>Cutoff</u>	Concrete wall on upstream face of dam.
<u>Grout Curtain</u>	None

h. Diversion and Regulating Tunnel

None

i. Spillway.

Main

<u>Type</u>	Concrete weir
<u>Length of Weir (feet)</u>	11.4
<u>Crest Elevation (feet above msl.)</u>	1392.0
<u>Upstream Channel</u>	Reservoir
<u>Downstream Channel</u>	Concrete paving across top of dam and down ramp to toe.

1. Spillway. (Cont'd.)

Auxiliary

<u>Type</u>	Broad-crested stone masonry weir
<u>Length of Weir (feet)</u>	144
<u>Crest Elevation</u>	Varies, El. 1392.1 to El. 1394.7
<u>Upstream Channel</u>	Reservoir
<u>Downstream Channel</u>	Natural Stream
<u>j. Regulating Outlets</u>	Two-foot wide sluice- way with stoplogs used to control flow.

SECTION 2  
ENGINEERING DATA

2.1 Design.

a. Data Available. There is no design information for Duck Harbor Pond Dam. Verbal descriptions provided by the Owner are in Paragraph 1.2g. No design calculations are available.

b. Design Features. The project is described in Paragraph 1.2a. The various features of the dam are shown on the photographs in Appendix C and on Plate E-2 in Appendix E.

c. Design Considerations. There is insufficient information to assess the design of the dam.

2.2 Construction.

a. Data Available. There is very little information concerning the original construction of the dam and subsequent modifications to it. Verbal descriptions given by the Owner are in Paragraph 1.2g.

b. Construction Considerations. There are insufficient data to assess the construction of the dam.

2.3 Operation. There are no formal records of operation. Records of inspections performed by the Commonwealth are available for the period from 1924 to 1965. A summary of the inspection reports is included in Appendix A. The Owner reported two instances when the dam has been overtopped to a significant depth. These are further discussed in Section 5.

2.4 Evaluation.

a. Availability. Available data were provided by the Bureau of Dams and Waterway Management, Department of Environmental Resources, Commonwealth of Pennsylvania (PennDER). The Owner was available for information during the visual inspection.

b. Adequacy. The type and amount of available design and other engineering data are very limited. The assessment of the dam is based on the combination of available data, visual inspection, performance history, hydrologic and hydraulic assumptions, and calculations developed for this report.

c. Validity. There is no reason to question the validity of the available data.

## SECTION 3

### VISUAL INSPECTION

#### 3.1 Findings.

a. General. The overall appearance of the dam and appurtenant structures is good. Noteworthy observations are described in the following paragraphs. The complete visual inspection checklist and sketch of the dam are presented in Appendix B. A profile of the top of the dam is included in Appendix B. Datum for the survey performed for this inspection was at the main spillway crest, Elevation 1392.0, as shown on USGS mapping. On the day of the inspection, the reservoir pool was 0.6 foot below the level of the main spillway crest.

b. Dry Stone Masonry Structure. This structure is in good condition. To the right of the spillway along the downstream edge, a few stones have been displaced. The top of the dam is covered with a thin layer of soil. At one area, this soil has washed through the dry masonry, leaving a depression on the top (Photograph F). Mature trees are growing along the downstream toe of the dry masonry. Clear seepage, estimated at 60 gpm, was flowing from beneath the stones to the left of the spillway ramp (Photograph B).

The concrete facing on the upstream side of the dry masonry is in good condition. A few shrinkage cracks were observed.

c. Appurtenant Structures. The main spillway, which is essentially a concrete paved section across the top of the dam, is in good condition. The concrete is slightly spalled at a few locations (Photograph D).

For the purposes of this report, the auxiliary spillway is considered to be the top of the dry masonry dam exclusive of the main spillway. This is discussed further in Section 5.

The outlet works is in excellent condition (Photograph E). It was noted that some of the outlet works discharge passing over the top outlet works stoplog was flowing into the dry masonry.

d. Reservoir Area. The watershed is mostly wooded with only minor rural development. Less than 10 percent is farm fields. There is one small dam in the watershed. It is less than 3 feet high and impounds negligible storage. The Pennsylvania Fish Commission maintains a public boat launching ramp along the shore of Duck Harbor Pond.

e. Downstream Conditions. As noted in Section 1, there is a breached dam immediately downstream from Duck Harbor Pond Dam. The stream extends from the breached dam for about 300 feet to a public road. Just downstream from the road, on the left bank of the stream, are two small mobile homes (trailers) about 5 feet above streambed. The mobile homes were of such size that they did not appear to be permanent residences. About 0.4 mile downstream of these mobile homes is a mill dam. The reservoir is completely silted in. The mill is the property of the Duck Harbor Lumber and Chemical Co. The Owner stated that it is a historic landmark because it contains the first Francis Turbine used in Pennsylvania. Although the mill is functionally operational, it is not used at present.

About 0.4 mile downstream of the mill, the stream flows under PA Route 191 and then generally parallels the road for 2.3 miles. The only building along this reach that is close to the stream is an abandoned schoolhouse. Along this reach, the stream also passes under a few rural roads. It was judged that, if the dam were to fail, probably only a few, if any, lives would be lost. Accordingly, a significant hazard classification has been assigned to Duck Harbor Pond Dam.

SECTION 4  
OPERATIONAL PROCEDURES

4.1 Procedure. The reservoir is normally maintained at the level of the spillway crest with excess inflows discharging over the spillway and into the downstream channel. The pool is maintained about 3 feet below spillway crest during the fall and winter months.

4.2 Maintenance of Dam. There are no established procedures for maintenance of the dam. Maintenance work has generally been performed on an unscheduled basis. Although the dam is checked daily by the Owner, no formal reports are maintained.

4.3 Maintenance of Operating Facilities. There is no established procedure for maintenance of the outlet works facilities.

4.4 Warning Systems in Effect. There is no emergency operation and warning system for the dam.

4.5 Evaluation of Operational Adequacy. Although the maintenance procedures are informal, the maintenance of the dam is generally good. The minor maintenance deficiencies noted in Section 3 are believed to be caused by unfamiliarity with dam maintenance requirements rather than with poor maintenance scheduling. The daily inspection program is good, but formal annual inspections by an experienced engineer are necessary to detect hazardous conditions before they might threaten the dam. An emergency operation and warning system is necessary to reduce the risk of dam failure should adverse conditions develop and to prevent loss of life should the dam fail.

## SECTION 5

### HYDROLOGY AND HYDRAULICS

#### 5.1 Evaluation of Features.

a. Design Data. There are no hydrologic or hydraulic design calculations available for Duck Harbor Pond Dam. According to a report prepared by the Commonwealth in 1917, the main spillway capacity was estimated at 50 cubic feet per second (cfs).

b. Experience Data. The Owner reported that the dam was overtopped by about 5 feet during the flood of May 1942 and during Tropical Storm Diane in 1955. The Owner stated that these depths of overtopping were his visual estimates and that high water elevations for these storms were not obtained. No damage was reported from these overtoppings.

#### c. Visual Observations.

(1) General. The visual inspection of Duck Harbor Pond Dam, which is described in Section 3, resulted in a number of observations relevant to hydrology and hydraulics.

(2) Dry Stone Masonry Structures. The entire top of dam appears capable of acting as an auxiliary spillway. The top of dam elevation was selected, based on the profile shown in Appendix B, as the elevation where the left abutment started to overtop (Elevation 1393.8). The top of the dam at the right abutment is Elevation 1394.7.

(3) Appurtenant Structures. No deficiencies relevant to hydrology or hydraulics were observed at the main spillway or outlet works.

(4) Reservoir Area. The one small dam in the watershed would have no effect on the hydrology at Duck Harbor Pond Dam. No conditions were observed in the reservoir area or watershed that might present a hazard to Duck Harbor Pond Dam.

(5) Downstream Conditions. If the dam were to fail, two small mobile homes and a sawmill that is presently not in use would be flooded. The mill dam is almost completely silted, and its possible failure during a failure of Duck Harbor Pond Dam would not increase the hazards downstream. Moreover, PA Route 191 would be flooded for a significantly long time. Downstream conditions indicate that a significant hazard classification is warranted for Duck Harbor Pond Dam. The two mobile homes are sufficiently close to the stream that they would be flooded before the full spillway capacity of Duck Harbor Pond Dam was being discharged.

d. Overtopping Potential.

(1) Spillway Design Flood. According to the criteria established by the Office of the Chief of Engineers (OCE), the Spillway Design Flood (SDF) for the size (intermediate) and hazard potential (significant) of Duck Harbor Pond Dam is between one-half of the Probable Maximum Flood (PMF) and the PMF. Since the dam and reservoir are on the low end of the intermediate size category, the 1/2 PMF was selected as the SDF for Duck Harbor Pond Dam. The watershed and reservoir were modeled with the U.S. Army Corps of Engineers' HEC-1DB computer program. A description of this computer program is included in Appendix D. The assessment of the hydrology and hydraulics is based on existing conditions, and the effects of future development are not considered.

(2) Summary of Results. Pertinent results are tabulated at the end of Appendix D. The analysis reveals that Duck Harbor Pond Dam can pass about 13 percent of the PMF before overtopping of the dam occurs.

(3) Spillway Adequacy. The criteria used to evaluate the spillway adequacy of a dam are described in Appendix D. Since the dam cannot pass the 1/2 PMF, which is the SDF, the spillway capacity is rated as inadequate.

## SECTION 6

### STRUCTURAL STABILITY

#### 6.1 Evaluation of Structural Stability.

##### a. Visual Observations.

(1) General. The visual inspection of Duck Harbor Pond Dam, which is described in Section 3, resulted in a number of observations relevant to structural stability. These observations are evaluated herein for the various features.

(2) Dry Stone Masonry Structure. The displaced stones may have been moved by vandals. Their replacement would improve the structural integrity of the dam. The soil that has washed through the top of the dam, thereby causing a depression, is of no concern. The Owner stated that the soil had been placed across the top solely to provide a roadbed for vehicular access. The few shrinkage cracks in the upstream facing are to be expected, since there are no joints in the concrete facing. These cracks are of no concern at present.

The root systems of large trees can grow through a dam and provide seepage paths. Because the upstream concrete facing is relatively new and because dry stone masonry is pervious, the trees at the top of the dam are presently not a hazard. If they are not removed in the near future, the roots could start to affect the upstream concrete wall.

Although the quantity of seepage to the left of the spillway ramp is significant, it is not concentrated. It appeared that much, if not all, of this seepage could have been the outlet works discharge flowing through the dry stone masonry walls of the outlet works tunnel. If this was the source of all the seepage, then the seepage would not be of any concern.

(3) Appurtenant Structures. The minor spalling along the main spillway walls is of no concern at present. No other deficiencies were observed at the outlet works or main spillway.

b. Design and Construction Data. No stability calculations for the dam are available. For this study the stability of the structure was analyzed with the pool at 1/2 PMF level. Full uplift was considered. For this condition, the resultant was determined to be within the middle third. The factor of safety against sliding was

determined to be adequate. The toe pressure was computed to be relatively small. Since foundation conditions are unknown, it is not possible to assess if the toe pressure is adequate. However, based on the age and history of the dam, toe pressures do not appear to be of concern. For this analysis, it was assumed that no scour from water flowing over the dam occurred at the toe of the dry masonry.

c. Operating Records. There are no operating records maintained for Duck Harbor Pond Dam and Reservoir. The operating procedures followed by the Owner do not indicate cause for concern relative to the structural integrity of the dam. There is no record of any stability problems at the dam.

d. Post-construction Changes. The modifications listed previously are maintenance repairs and do not adversely affect the structural stability of the dam.

e. Seismic Stability. Duck Harbor Pond Dam is located in Seismic Zone 1 where earthquake loadings are not considered to be significant for low dams with no readily apparent stability problems. Since no readily apparent stability problems were observed, the seismic stability of the dam is considered to be adequate.

SECTION 7  
ASSESSMENT, RECOMMENDATIONS, AND  
PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety.

(1) Based on criteria established for these studies, Duck Harbor Pond Dam is judged to be in good condition. The recommended Spillway Design Flood (SDF) for the size and hazard classification of the dam varies between the 1/2 PMF and the PMF. The selected SDF is the 1/2 PMF. The existing spillway will pass about 13 percent of the PMF before overtopping of the dam occurs. The spillway capacity is rated as inadequate.

(2) Several deficiencies were observed, all of which are considered to be minor.

(3) A summary of the features and observed deficiencies is as follows:

<u>Feature</u>	<u>Observed Deficiency</u>
Dry Stone Masonry Structure	A few stones missing from top; trees at toe, seepage.
Spillway	Minor spalling.

b. Adequacy of Information. The information available is such that an assessment of the condition of the dam can be inferred from the combination of available data, visual inspection, past performance, and computations performed as part of this study.

c. Urgency. The recommendations in Paragraph 7.2 should be implemented without delay.

d. Necessity for Further Investigations. Further investigations by the Owner will not be required to accomplish the remedial measures outlined in Paragraph 7.2.

7.2 Recommendations and Remedial Measures.

a. The following remedial measures, listed in approximate order of priority, are recommended to be undertaken by the Owner without delay:

(1) As part of the regular maintenance program, remove trees growing along the toe of the dam and replace the missing stones at the top of the dam.

(2) Expand the regular inspection program to include monitoring of concrete spalling and seepage. Take appropriate action if conditions worsen.

b. In addition, the Owner should institute the following operational and maintenance procedures:

(1) Develop a detailed emergency operation and warning system for Duck Harbor Pond Dam. When warnings of a major storm are given by the National Weather Service, the Owner should activate the emergency operation and warning system.

(2) During periods of unusually heavy rains, provide round-the-clock surveillance of the dam.

(3) As presently required by the Commonwealth, initiate a program of formal annual inspections by a professional engineer experienced in the design and construction of dams. Utilize the inspection results to determine if remedial measures are necessary.

APPENDIX A  
CHECKLIST - ENGINEERING DATA

**CHECKLIST**  
**ENGINEERING DATA**  
**DESIGN, CONSTRUCTION, AND OPERATION**  
**PHASE I**

NAME OF DAM: Dam Haipan River

NDI ID NO.: PF-20144 DER ID NO.: 64-54

Sheet 1 of 4

ITEM	REMARKS
AS-BUILT DRAWINGS	None in the case See Project File 2
REGIONAL VICINITY MAP	See Project File 1
CONSTRUCTION HISTORY	None
TYPICAL SECTIONS OF DAM	See Project File 2 None in Project File
OUTLETS: Plan Details Constraints Discharge Ratings	None

A-1

## ENGINEERING DATA

Sheet 2 of 4

ITEM	REMARKS
RAINFALL/RESERVOIR RECORDS	None
DESIGN REPORTS	None
GEOLOGY REPORTS	None
DESIGN COMPUTATIONS: Hydrology and Hydraulics Dam Stability Seepage Studies	None
MATERIALS INVESTIGATIONS: Boring Records Laboratory Field	None
POSTCONSTRUCTION SURVEYS OF DAM	None

## ENGINEERING DATA

Sheet 3 of 4

ITEM	REMARKS
BORROW SOURCES	Unknown
MONITORING SYSTEMS	None
MODIFICATIONS	None made - None reported
HIGH POOL RECORDS	Reported in 1942 & 1945, Current depths
POSTCONSTRUCTION ENGINEERING STUDIES AND REPORTS	1917 Report by Committee on No recommendations or modifications.
PRIOR ACCIDENTS OR FAILURE OF DAM: Description Reports	None

A-3

## ENGINEERING DATA

Sheet 4 of 4

ITEM	REMARKS
MAINTENANCE AND OPERATION RECORDS	No. 10000. Records
SPILLWAY: Plan Sections Details	Plan 10000 See Table E-2
OPERATING EQUIPMENT: Plans Details	None
PREVIOUS INSPECTIONS Dates Deficiencies	1920 (by Owner) - Minor Deficiencies in concrete. 1924 - Permanent - Minor Deficiencies. 1928 - Minor Deficiencies. 1930 - Minor Deficiencies. 1933 - Minor Deficiencies. 1933 - Spillway Dam - Minor Deficiencies. 1933 - Minor Deficiencies.

A-4

## ENGINEERING DATA

Sheet 4a of 4

ITEM	REMARKS
Previous Traces (Continued)	
1937 - Log. rock debris along crest. Larger - "Downstream side over spilling submerged. All material flowing through crevices."	
1941 - Top at about 11 ft. Settles. Leaks	
1948 - Through "Servicey". Depth about 10 ft. Stoplogs at work Pool very low "right time". Just before faced with concrete. New gate control timbers necessary removed. Top at about low. (Repairs delayed).	
1952 - Good Condition.	
1965 - Top at about 10 ft. Spillway open pool, weathered, and reduced	
	"Wear and tear on top - will have to reconstruct. Reconstruction service will be given. Possible leakage at top. (Repairs proposed).

APPENDIX B

CHECKLIST - VISUAL INSPECTION

CHECKLIST

VISUAL INSPECTION

PHASE I

Name of Dam: Duck Harbor Stone County: Wayne State: Pennsylvania  
NDI ID No.: PA-00144 DER ID No.: 64-54  
Type of Dam: Dry Hazard Category: Significant  
Date(s) Inspection: 14 April 1991 Weather: Cloudy / Light Rain Temperature: 54° F  
Soil: Moist to wet

Pool Elevation at Time of Inspection: 1391.4 msl/Tailwater at Time of Inspection: 1381.3 msl

Inspection Personnel:

J. Hill (Duck Harbor Engineer & Chemist)  
D. Wolf (GRC)  
D. Eberle (GRC)

A. Whitman (GRC) Recorder

## CONCRETE/MASONRY DAMS

Sheet 1 of 2

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	60' from bencath stones to left of spillway ramp	Source may be water works opening.
JUNCTION OF STRUCTURE WITH: Abutment Embankment Other Features	No deficiencies	
DRAINS	None	
WATER PASSAGES	4' x 6.2' opening through berm of concrete paving on bottom.	No deficiencies
FOUNDATION	(None)	

## CONCRETE/MASONRY DAMS

Sheet 2 of 2

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
<del>DRY MASONRY</del> CONCRETE SURFACES: Surface Cracks Spalling	None	Top or non could function as an auxiliary spillway.
STRUCTURAL CRACKING	None visible Concrete face	
ALIGNMENT:	Vertical	Horizontal - upstream
	Horizontal	Side is irregular due to poor alignment.
		Vertical - see point 1
MONOLITH JOINTS	No vertical joints	in upstream concrete
		Facing
CONSTRUCTION JOINTS	No joints	on upstream concrete
STAFF GAGE OR RECORDER		None

B - 1

OUTLET WORKS

Sheet 1 of 1

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPAILING OF CONCRETE SURFACES IN OUTLET CONDUIT	Dry Magma / Through dry, No visible signs of cracking.	Good Condition
INTAKE STRUCTURE	Sluiceway / Good Condition	
OUTLET STRUCTURE	None	
OUTLET CHANNEL	None, No signs.	
EMERGENCY GATE	Wooden, No signs.	

## UNGATED SPILLWAY

Sheet 1 of 1

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS	
CONCRETE WEIR	Good Condition		
APPROACH CHANNEL	Reservoir		
DISCHARGE CHANNEL	Concrete Poured across river or stream and down banks	Riverine conditions along concrete and down banks	
BRIDGE AND PIERS	None in site		

## INSTRUMENTATION

Sheet 1 of 1

VISUAL EXAMINATION OF	OBSEERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None	None
OBSERVATION WELLS		
WEIRS		
PIEZOMETERS		
OTHER	None	None

## DOWNSTREAM CHANNEL

Sheet 1 of 1

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION: Obstructions Debris Other	Present in river Amount 200 debris in channel, other channel	
SLOPES	Rain wash, mud erosion on channel	
APPROXIMATE NUMBER OF HOMES AND POPULATION	2 small houses presently occupied none other visible	

## RESERVOIR AND WATERSHED


Sheet 1 of 1

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	No erosion observed.	Minor soil erosion.
SEDIMENTATION	No sedimentation observed.	Minor sedimentation.
WATERSHED DESCRIPTION	90% cropland 10% rangeland Minor urban development	

BY DRE DATE 9-21-81 SUBJECT DUCK HARBOR POND DAM  
CHKD BY \_\_\_\_\_ DATE \_\_\_\_\_ SHEET NO \_\_\_\_\_ OF \_\_\_\_\_  
JOB NO 0596.51


CHKD BY \_\_\_\_\_ DATE \_\_\_\_\_

SHEET NO.        OF         
JOB NO. 0596.5A



DATE OF INSPECTION: 14 APRIL 81  
POOL ELEVATION: 1391.4

GRAVEL ROAD



SCALE: 1 IN. = 20 FT.

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

DUCK HARBOR POND DAM

DUCK HARBOR LUMBER  
AND CHEMICAL CO., INC.

RESULTS OF  
VISUAL INSPECTION

MAY 1981

EXHIBIT B-1

APPENDIX C  
PHOTOGRAPHS

DUCK BARBOR POND DAM



A. Downstream Face and Outlet Works



B. Downstream Face

DUCK HARBOR POND DAM




C. Top of Dam



D. Spillway


DUCK HARBOR POND DAM



E. Outlet Works



F. Depression in Top



APPENDIX D  
HYDROLOGY AND HYDRAULICS

## APPENDIX D

### HYDROLOGY AND HYDRAULICS

#### Spillway Capacity Rating:

In the recommended Guidelines for Safety Inspection of Dams, the Department of the Army, Office of the Chief of Engineers (OCE), established criteria for rating the capacity of spillways. The recommended Spillway Design Flood (SDF) for the size (small, intermediate, or large) and hazard potential (low, significant, or high) classification of a dam is selected in accordance with the criteria. The SDF for those dams in the high hazard category varies between one-half of the Probable Maximum Flood (PMF) and the PMF. If the dam and spillway are not capable of passing the SDF without overtopping failure, the spillway capacity is rated as inadequate. If the dam and spillway are capable of passing one-half of the PMF without overtopping failure, or if the dam is not in the high hazard category, the spillway capacity is not rated as seriously inadequate. A spillway capacity is rated as seriously inadequate if all of the following conditions exist:

- (a) There is a high hazard to loss of life from large flows downstream of the dam.
- (b) Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure.
- (c) The dam and spillway are not capable of passing one-half of the PMF without overtopping failure.

#### Description of Model:

If the Owner has not developed a PMF for the dam, the watershed is modeled with the HEC-1DB computer program, which was developed by the U.S. Army Corps of Engineers. The HEC-1DB computer program calculates a PMF runoff hydrograph (and percentages thereof) and routes the flows through both reservoirs and stream sections. In addition, it has the capability to simulate an overtopping dam failure. By modifying the rainfall criteria, it is also possible to model the 100-year flood with the program.

## APPENDIX D

## DELAWARE

## River Basin

Name of Stream: LITTLE EQUINUNK CREEKName of Dam: DUCK HOLLOW ROADNDI ID No.: PA-00144DER ID No.: 64-54Latitude: N 41°45.2' Longitude: W 75°12.3'Top of Dam Elevation: 1,293.5Streambed Elevation: 1,351.3 Height of Dam: 12.5 ftReservoir Storage at Top of Dam Elevation: 1,104 acre-ftSize Category: INTERMEDIATEHazard Category: SIGNIFICANT (see Section 5)Spillway Design Flood: VARIOUS 1/2 PNT. - 1.11 EUPSTREAM DAMS

Name	Distance from Dam (miles)	Height (ft)	Storage at top of Dam Elevation (acre-ft)	Remarks
<u>CHE</u>	<u>STRUCTURE</u>	<u>AS NOTED OR</u>		
<u>PLATE E-1</u>	<u>only 2-3' high. Not</u>			
	<u>SIGNIFICANT 22 APR 1985.</u>			

DOWNSTREAM DAMS

<u>BREAKAWAY</u>	<u>600 FT.</u>	<u>N/A</u>	<u>N/A</u>	<u>NOT SEEN</u>
<u>MILL DAM</u>	<u>0.4</u>	<u>N/A</u>	<u>SILTED TO TOP OF 1 FT.</u>	<u>TO 1 FT.</u>

DELAWARE River Basin  
 Name of Stream: LITTLE EQUINUNK CREEK  
 Name of Dam: Lucie Hersee Dam  
DETERMINATION OF PMF RAINFALL & UNIT HYDROGRAPH

UNIT HYDROGRAPH DATA:

Sub-area	Drainage Area (square miles)	Cp (1)	Ct (2)	L miles (3)	L <sub>ca</sub> miles (4)	L' miles (5)	Tp hours (6)	Map Area (7)	Plate (8)
A	3.45	0.45	1.23	N/A	N/A	1.9	1.81	1	1
Total	3.45								

(1) & (2): Snyder Unit Hydrograph coefficients supplied by Baltimore District, Corps of Engineers on maps and plates referenced in (7) & (8)

The following are measured from the outlet of the subarea:

(3): Length of main watercourse extended to divide

(4): Length of main watercourse to the centroid

The following is measured from the upstream end of the reservoir at normal pool:

(5): Length of main watercourse extended to divide

(6):  $T_p = C_t \times (L \times L_{ca})^{0.3}$ , except where the centroid of the subarea is located in the reservoir. Then

$$T_p = C_t \times (L')^{0.6}$$

Initial flow is assumed at 1.5 cfs/sq. mile

Computer Data: QRCSN = -0.05 (5% of peak flow)

$$RTIOR = 2.0$$

RAINFALL DATA:

PMF Rainfall Index = 21.0 in., 24 hr., 200 sq. mile  
 Hydromet. 40 Hydromet. 33  
 (Susquehanna Basin) (Other Basins)

Zone: N/A 1

Geographic Adjustment

Factor: N/A 1.0

Revised Index

Rainfall: N/A 21.0

RAINFALL DISTRIBUTION (percent)

Time	Percent
6 hours	111
12 hours	123
24 hours	123
48 hours	142
72 hours	-
96 hours	-

Data for Dam at Outlet of Subarea A

Name of Dam: Duck Helder Dam

<u>SPILLWAY DATA:</u>	<u>Existing Conditions</u>	<u>Design Conditions</u>
Top of Dam Elevation	1393.8	
Spillway Crest Elevation	1392.0	
Spillway Head Available (ft)	1.8	
Type Spillway	Sheet-creast, 20%	
"C" Value - Spillway	3.1	
Crest Length - Spillway (ft)	11.4	
<u>Spillway</u> Peak Discharge (cfs)	85	
Auxiliary Spillway Crest Elev.	1393.1	
Auxiliary Spill. Head Avail. (ft)	45.0	
Type Auxiliary Spillway	Crest-creast	
"C" Value - Auxiliary Spill. (ft)	HEC-1 DE	
Crest Length - Auxil. Spill. (ft)	PROGRESS	
Auxiliary Spillway		
Peak Discharge (cfs)		
Combined Spillway Discharge (cfs)		

### Spillway Rating Curve:


<u>OUTLET WORKS RATING:</u>	<u>Outlet 1</u>	<u>Outlet 2</u>	<u>Outlet 3</u>
<u>Equation:</u>	<u>Net Head</u>	<u>Head</u>	<u>Head</u>
Invert of Outlet	<u>SI</u>	<u>ft</u>	<u>ft</u>
Invert of Inlet			
Type			
Diameter (ft) = D			
Length (ft) = L			
Area (sq. ft) = A			
N			
K Entrance			
K Exit			
K Friction = $29.1 N^2 L / R^4 / 3$			
Sum of K			
$(1/K)^{0.5} = C$			
Maximum Head (ft) = HM			
$Q = CA\sqrt{2g(HM)}(cfs)$			
Q Combined (cfs)	160		

BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHKD BY \_\_\_\_\_ DATE \_\_\_\_\_

SUBJECT \_\_\_\_\_  
\_\_\_\_\_


SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_  
JOB NO. \_\_\_\_\_

DUCK HARBOR POND  
OUTLET WORKS



- 1381.8 AT DOWNSTREAM END

ENTRANCE - LOOKING downstream.



$$Q = C L H^{3/2} \quad C = 3.1 \quad H = 9' \quad L = 2'$$
$$Q = \underline{167 \text{ CFS}} \approx \underline{160 \text{ CFS}}$$

(approach effects significant)

D-5

Data for Dam at Outlet of Subarea A

Name of Dam: Duck Hillside Pond

STORAGE DATA:

<u>Elevation</u>	<u>Area (acres)</u>	<u>Storage</u>		<u>Remarks</u>
		<u>million gals</u>	<u>acre-ft</u>	
1381.3 =ELEVO*	0	0	0	
1392.0 =ELEV1	204 =A1		728 =S1	LEGS
1392.7	208		872	
1393.4	211		1,019	
1393.7	213		1,082	
1393.8	214		1,104	Tot. on 20
1394.0	215		1,137	
1394.7	216		1,295	
1400.2 **	243			

\* ELEVO = ELEV1 - (3S<sub>1</sub>/A<sub>1</sub>)

\*\* Planimetered contour at least 10 feet above top of dam

Reservoir Area at Normal Pool is 9 percent of subarea watershed.

BREACH DATA: Not Used

See Appendix B for sections and existing profile of the dam.

Soil Type from Visual Inspection: \_\_\_\_\_

Maximum Permissible Velocity (Plate 28, EM 1110-2-1601) \_\_\_\_\_ fps  
(from  $Q = CLH^{3/2} = V \cdot A$  and depth =  $(2/3) \times H$ ) &  $A = L \cdot \text{depth}$

$H_{MAX} = (4/9 V^2/C^2) =$  \_\_\_\_\_ ft.,  $C =$  \_\_\_\_\_ Top of Dam El. = \_\_\_\_\_

$H_{MAX} + \text{Top of Dam El.} =$  \_\_\_\_\_ = FAILEL  
(Above is elevation at which failure would start)

Dam Breach Data:

BRWID = \_\_\_\_\_ ft (width of bottom of breach)  
Z = \_\_\_\_\_ (side slopes of breach)  
ELBM = \_\_\_\_\_ (bottom of breach elevation, minimum of  
zero storage elevation)  
WSEL = \_\_\_\_\_ (normal pool elevation)  
T FAIL = \_\_\_\_\_ mins = \_\_\_\_\_ hrs (time for breach to  
develop)

BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHKD BY \_\_\_\_\_ DATE \_\_\_\_\_

SUBJECT \_\_\_\_\_

SHEET NO \_\_\_\_\_ OF \_\_\_\_\_  
JOB NO \_\_\_\_\_

SELECTED Computer Output

HEC-1 DB MODEL

	PAGE
1. INPUT	D-8
2. Summary of PEAK Flows	D-9
3. Duck Harbor Pond Dam	D-10

FLOOD HYDROGRAPHY PACKAGE (HEC-1)  
DAM SAFETY VERSION JULY 1978  
LAST MODIFICATION 01 APR 80

NATIONAL DAM INSPECTION PROGRAM

	A1		LITTLE FOONUNK CREEK		DUCK HARBOR POND DAM		C		0		-4		0	
1			6	100	0	15	0	0	0	0	0	0	0	0
2	2	42	5	1	6	1								
3	4	45	5	1	5	1								
4	6	8	1	1	6	1								
5	7	7	1	1	5	1								
6	8	0	1	1	4	1								
9	10	K1	1	1	1	1								
11	12	P	1	1	1	1								
13	14	X	1	1	1	1								
15	16	X	-1.5	-0.05	2.0	1								
17	18	Y	1	1	1	1								
19	20	Y1	1	1	1	1								
21	22	SA	0	204	248									
23	24	SE1181.3	1392	14.00										
		SS 1192	11.6	3.61	1.65									
		SD1393.8												
		SL 0												
		SD1192.1	1392.7	1393.6	1393.67	1393.70	1393.75	1393.8	1394	1395	1395	1396	1396	1396
		X 00												

D-08

NOTE. \$L + \$V CARDS ARE USED TO MODEL THE AUXILIARY SPILLWAY. THE FLOW COMPUTED USING THE \$L + \$V CARDS IS ADDED TO THE FLOW COMPUTED FROM THE \$ CARD. THE DRAIN OR OVERTOPPING IS THE DIFFERENCE BETWEEN THE FLOOR ELEVATION AND THE ELEVATION SHOWN ON THE \$D CARD. THE DEPTH OF FLOW OVER THE TOP OF THE DAM, AS MEASURED FROM THE LOW ELEVATIONS AND THE \$V CARD, IS GREATER THAN THE COMPUTER DEPTH OF OVERTOPPING.

PFAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-FATIGUE COMPUTATIONS  
 FLOW IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS			
				RATIO 1 1.00	RATIO 2 .50	RATIO 3 .40	RATIO 4 .30
HYDROGRAPH AT	1 ( 0.94)	1 ( 106.20)	1 ( 6920.	34.64. 08.10)(	2771. 78.49)(	2070. 58.86)(	1386. 39.24)(
ROUTED TO	1 ( 0.95)	1 ( 152.12)	1 ( 5372. 64.42)	2275. 47.03)(	1661. 30.09)(	1063. 14.57)(	515. 121. 3.62)(

SUMMARY OF DAM SAFETY ANALYSIS						
DUCK HARBOR POND DAM						
PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CFSI	TOP OF DAM	TOP OF DAM	TIME OF FAILURE . HOURS
		1392.00 729.	1397.00 729.	1393.80 1101. 0.	1393.80 1101. 0.	1H 7.
RATIO OF RESERVOIR V.S. LEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OFF TOP HOURS	MAX OUTFLOW CFS	TIME OF FAILURE . HOURS
1.00	1398.26	4.46	2110.	5372.	24.50	43.25
.50	1396.76	2.46	1644.	2275.	20.25	44.00
.40	1395.75	1.95	1531.	1661.	18.75	44.25
.30	1395.08	1.38	1403.	1063.	16.75	44.75
.20	1394.48	.68	1251.	515.	13.50	45.75
.10	1393.61	0.00	1042.	121.	0.00	48.25

BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHKD BY \_\_\_\_\_ DATE \_\_\_\_\_

SUBJECT \_\_\_\_\_

SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_  
JOB NO. \_\_\_\_\_

I

Summary of Pertinent Results

PMF

$\frac{1}{2} \text{ PMF} = \text{SDF}$


RAINFALL (inches)	23.86	N/A
RUNOFF (inches)	21.69	10.85
PEAK INFLOW (CFS)	6,929	3,464

Duck Harbor Pond Dam

PEAK OUTFLOW (CFS)	5,372	2,275
Depth of Overtopping* (FT)	4.46	2.46
Duration of Overtopping (HRS)	24.50	20.25


\* Above EL. 1393.8


D-11



APPENDIX E

PLATES





SCALE: 1 IN. = 10 FT.

**PHASE T INSPECTION**

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

## DUCK HARBOR POND DAM

DUCK HARBOR LUMBER  
AND CHEMICAL CO., INC

## PLAN AND SECTIONS

MAY 1981

**PLATE E-2**

APPENDIX F  
GEOLOGY

## DUCK HARBOR POND DAM

### APPENDIX F

#### GEOLOGY

Duck Harbor Pond Dam is located in Wayne County within the Appalachian Plateau Physiographic Province. The most pronounced topographic feature in the area is Camelback Mountain, which is part of the Pocono Plateau Escarpment. The escarpment has a well-defined, southwestward trend from Camelback Mountain, but it is irregular between Camelback Mountain and Mt. Pocono, which lies to the north. Streams east of the escarpment drain directly to the Delaware River, while those to the west drain to the Lehigh River.

The Pocono Plateau Section lies to the west of the escarpment. This area is relatively flat, with local relief seldom exceeding 100 feet. The topography has been greatly influenced by continental glaciation. Many features were created by deposition of glacial materials. The entire plateau lacks well-developed drainage.

East of the escarpment is the Glaciated Low Plateaus Section of the province. This area is characterized by preglacial erosional topography with locally-thick glacial deposits. Local relief is generally 100 to 300 feet.


Bedrock units of the sections described above are the lithified sediments of offshore marine, marginal marine, deltaic environments, and fluvial environments associated with the Devonian Period. These units include siltstones of the Mahantango Formation, siltstones and shales of the Trimmers Rock Formation, and seven mapped members of the Catskill Formation. These members include sandstones, siltstones, and shales of the Towamensing Member; sandstone, siltstone and shale of the Walcksville Member; sandstones, siltstones and shale of the Beaverdam Run Member; sandstone and shale in the Long Run Member; sandstones and conglomerates in the Packerton Member; sandstones and some conglomerates in the Poplar Gap Member; and sandstones and conglomerates in the Duncannon Member.

Duck Harbor Pond Dam is underlain by the Catskill Formation. The Catskill Formation is predominantly red to brownish gray shales and sandstone with interbedded siltstones and conglomerates. Sandstones present are thickbedded, fine-to coarse-grained and exhibit very low primary porosity due to a clay and silica matrix. Effective porosity results from fractures and parting planes.

The rocks are well-indurated and generally are not susceptible to slope failure; however, the presence of well-developed bedding and joint planes will result in some rockfall from vertical and high-angle cut slopes.

Bedrock is entirely overlain by glacial till of Late Wisconsin Age. This till is an unsorted mixture of clay, silt, sand, and gravel. It is moderately cohesive and is generally derived locally from the sandstones of the Catskill Formation. Thickness of the till varies from 5 to 75 feet.

Foundation conditions at the dam are unknown.



PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

## DUCK HARBOR POND DAM

DUCK HARBOR LUMBER  
AND CHEMICAL CO., INC.

## GEOLOGIC MAP

SCALE: 1 IN. = 4 MILES

MAY 1981

**EXHIBIT F-1**

